LODHA
BUILDING A BETTER LIFE

Policy No.	PCA – 06
Date W.E.F.	23.03.2013
Virsion No	1
Revision Date	29.06.2022
Pages	1 of 1

LIST OF ALLOWABLE WASTAGES FOR LODHA SUPPLIED MATERIAL (LSM)

Sr No	Materials	Allowable % Wastage
1	Cement	5%
2	Sand	10%
3	Aggregate	5%
4	Reinforcement steel (not applicable for cut & bent steel)	3%
5	Pre-cut & bent steel	0.5%
6	RMC	1%
7	Bricks	15%
8	Blocks	5%
9	Rubble	10%
10	Admixtures / WP Chemicals	3%
11	Italian / Agglomerated Marble (slab, not 'cut to size' option)	17%
12	Marble (slab, not 'cut to size' option)	15%
13	Marble ('cut to size' option)	7%
14	Granite	15%
15	Kota	10%
16	Cudapah	10%
17	Vitrified tiles / Cut-to-size marble tiles	Refer Annexure
18	Ceramic	Refer Annexure
19	Pavers	5%
20	Glass mosaic	5%
21	Wooden floor	3%
22	Shahabad	10%
23	China mosaic	10%
24	Plumbing & Sanitary accessories	0%
25	Electrical accessories	0%
26	Wires	5%
27	Door Fittings	0%

Note : 1) Flooring Design wastage for Entrance lobbies may vary depending up the pattern

2) Reinforcement steel wastages is considered without rolling margin.

3) This does not include the quantity required to be handed over to HFM as per 'Construction Materials required to be ordered excess and handed over to FM at time of project handover'.

ANNEXURE

Type	Area	Location	Allowable Wastages		
			Design	Handling	Total
Vetrified	Living Dining Passage and Bedroom	Flooring	6%	3%	9%
Vetrified	Kitchen	Flooring	5%	3%	8%
Ceramic	Kitchen -BELOW PLAT FORM	Dado	5%	15%	20%
Vetrified	Master Toilet	Flooring	5%	3%	8%
Vetrified / Ceramic	Master Toilet	Dado	10%	3%	13%
Vetrified / Ceramic	Common Toilet	Flooring	8%	3%	11%
Vetrified / Ceramic	Common Toilet	Dado	10%	3%	13%
Vetrified	UTILITY	Flooring	5%	15%	20%

Note -

1 Areawise Theoretical wastages to be calculated based on the drawings and ensure that the wastages are below the allowable percentages specified in the table above

2 Wastages to be reviewed after completion of DCU and ensure that the wastages are below the theoretical wastages calculated in 1 above