LIST OF ALLOWABLE WASTAGES FOR LODHA SUPPLIED MATERIAL (LSM)

Sr No	Materials	Allowable % Wastage
1	Cement	5%
2	Sand	10%
3	Aggregate	5%
4	Reinforcement steel (not applicable for cut & bent steel)	3%
5	Pre-cut & bent steel	0.5%
6	RMC	1%
7	Bricks	15%
8	Blocks	5%
9	Rubble	10%
10	Admixtures / WP Chemicals	3%
11	Italian / Agglomerated Marble (slab, not 'cut to size' option)	17%
12	Marble (slab, not 'cut to size' option)	15%
13	Marble ('cut to size' option)	7%
14	Granite	15%
15	Kota	10%
16	Cudapah	10%
17	Vitrified tiles / Cut-to-size marble tiles	5%
18	Ceramic	10%
19	Pavers	5%
20	Glass mosaic	5%
21	Wooden floor	3%
22	Shahabad	10%
23	China mosaic	10%
24	Plumbing & Sanitary accessories	0%
25	Electrical accessories	0%
26	Wires	5%
27	Door Fittings	0%

Note : 1) Flooring Design wastage for Entrance lobbies may vary depending up the pattern

2) Reinforcement steel wastages is considered without rolling margin.

3) This does not include the quantity required to be handed over to HFM as per 'Construction Materials required to be ordered excess and handed over to FM at time of project handover'.