दुरध्वनी : २५३३ १२११
२५३३ १५९०

# ठाणे महानगरपालिका

महानगरपालिका भवन, डॉ. अल्मेडा रोड, चंदनवाडी, पाचपाखाडी, ठाणे-४०० ६०२.
THE MUNICIPAL CORPORATION OF THE CITY OF THANE

संदर्भ क्र./ठा.म.पा./ दिनांक / / २००
Ref/T.M.C/C.F.O/M.468/49 Date 15/06/2010

To,
The Asst. Director of Town Planning
Thane Municipal Corporation,
Thane

Sub: Grant of N.O.C. stipulating, Fire Protection & Fire Fighting requirements for the proposed Development on land bearing Gut No.61/1, 61/2 at Village Chitalsar (Manpada) Tal & Dist, Thane.
**For Ascent Construction Pvt. Ltd. Through Director Shri.Pravin H. Doshi**

Re: i. A letter from an Architect Shri. Subhash Gupte dt. 01/06/2010
ii. V.P. No. 88/142
iii. Site Visit Dt 10/06/2010

Dear Sir,

Proposal is to construct the Residential building on Gut No.61/1, 61/2 at Village Chitalsar Manpada Tal & Dist, Thane.

The architectural plans of proposed buildings are referred to the Chief Fire Officer, Thane Fire Brigade, Thane by an Architect **Shri. Subhash Gupte, Gupte College, Opp. Bhakti Mandir, Panchpakhadi, Thane (W) 400 602.** The plans of these buildings are scrutinized by this department as per existing buildings by-laws from the point of fire safety and means of escape.

Observations and Directives of Chief Fire Officer, Thane Fire Brigade, Thane for the said proposal are given below.

**OBSERVATIONS & DIRECTIVES**

A) Plot under reference is 44133.20 m2 in area.

B) The said plot is sub divided in to sub plot A & sub plot B by 20.m. wide existing D.P.Road.

C) Total 18 buildings are proposed on the above reffered plot.

D) Out of 18 buildings 9 buildings are proposed on sub plot A & 9 buildings are proposed on sub plot B.

E) Architect has submitted plans of 5 buildings namely building No. 7 & 8 in sub plot A & building No. 3, 5 & 6 in sub plot B.

F) Architectural plans of above 05 buildings are scrutinized by this department as per existing building by laws & remarks are attach here with.

**Building No. 7 & 8 on sub plot A**

G) Sub plot A on which bldg. No. 7 & 8 are propose is approachable by 20.00 m. wide existing D.P. Road from north side.

H) Single entry gate is propose on north side for for the bldg. No. 7 & 8 on the D.P. Road.

I) Propose bldg. no. 7 & 8 are stilt + 11th floors which are 36.05m. from ground level.

Thane Municipal Corporation of the City of Thane ठाणे महानगर पालिका अग्निशमन दल Fire Brigade

J) Both the buildings are attached with each other from east / west side.

K) Adequate open space is proposed around both the buildings.

L) Two enclose staircases having the width of 1.5m. is propose in buildings No. 7 & 8.

M) Three lifts are proposed in bldg. No. 7 & 8 out of which two are attached with each other.

Total Bldg. – 05
03 Bldg. – 20 floor
02 Bldg. - 11 floor

N) Required space for refuge area is kept on 8th floor for building No. 7 & 8 .

O) Locations of meter room, substation & D.G. set is not marked on the plan.

P) Locations of required firefighting measures are not marked on the plan.

Q) **Building no. 3, 5 & 6 ( sub plot B.)**

1) Building 3, 5 & 6 are proposed on the sub plot B.

2) sub plot B is approachable by 20m. wide existing D.P. Road from south side.

3) All the 3 buildings i.e. building no. 3, 5 & 6 are approachable by 10.0 m. wide propose road from west side.

4) Adequate open spaces are proposed on the ground floor for all the 3 buildings.

5) Propose all the 3 buildings are of stilt + 20 floor i.e. 59.45 m. in height from ground level.

6) Stilt floor of all the 3 buildings will be use exclusively for parking & remaining all the floors will be use for residential purposes.

7) A single enclose staircase having the width of 1.5 m. is proposed in each building.

8) Two lifts are propose in each building. Both the lift of each buildings are attached with each other.

9) Required space for refuse area is kept on 8th , 13th & 18th floor of bldg. no. 3, 5 & 6 .

10) Locations of meter room, substation & D.G. set is not marked on the plan for any building.

11) Required firefighting measures are not marked on the plan for any building.

Considering the above situation following fire prevention and protection measures are recommended in all the 5 buildings i.e. in bldg. no. 7 & 8 which are propose is sub plot A & in bldg. no. 3, 5 & 6 which are proposed on sub plot B.

**MAIN ROAD/D.P. ROAD. :**

Sub plot A is approachable by 20.0 m. wide Existing road from north side. and the proposed building i. e. 7 & 8 are approachable from the said road.
Sub plot B is approachable by 20.0 m. wide Existing road from south side and 10.0m. wide D.P. road from west side. the proposed building i. e. 3, 5 & 6 are approachable from the said road.

**SUGGESTIONS :**

No additional suggestions are given by this dept. neither for main road nor for internal road.

**OPEN SPACE :-**

Open space around proposed high rise Residential building is as follows:

| | | OPEN SPACE | | | |
|---|---|---|---|---|---|
| | | Sub plot A | Sub plot B | | |
| S.No. | Side | Bldg. No.7 &8 | Bldg. No.3 | Bldg. No.5 | Bldg. No. 6 |
| 1 | North | 6.00 mt | 6.00 mt | 6.00 mt | 6.00 mt |
| 2 | South | 13.00 mt . | 6.00 mt | 6.00 mt | 6.00 mt |
| 3 | East | 11.75 mt. | 6.00 mt | 13.42 mt | 6.00 mt |
| 4 | West | 6.00 mt | 8.20 mt. | 6.00 mt | 6.00 mt |

**SUGGESTIONS :**

i. Minimum 6.0 mtr. Open space around the bldg. must be maintained free of all encroachment / obstructions / parking for the easy movement of fire appliances and same shall be capable of taking the load of fire engine upto 45.0 tone.

ii. Parking shall not be allowed in the driveway.

iii. Open spaces shall be paved from all the sides.

iv. UG Tank shall not be proposed in the minimum required open spaces.

v. Turning circle radius on any corner shall not be less than 10.0 meter.

**ENTRY GATES :**

1. Two gates are proposed for the entire sub plot A, which are on the north side.
2. Two gates are proposed for the entire sub plot B, which are on the west & south side.

**SUGGESTIONS :**

1. Minimum 1 entry gate and 1 exit shall be provided for the proposed high rise residential buildings.
2. Entry gates shall be located preferably attached to the approach Roads.
3. The width and hight clearance of the entry gate shall not be less than 5 mtrs.

**HEIGHT , FLOOR AREA & OCCUPANCY :**

The height and built-up are & occupancy of each building are as follows :

On sub plot A

| No | Bldg.No | FLOOR | FLOOR AREA | OCCUPANCY |
|---|---|---|---|---|
| 1 | 7 | Stilt | | Parking |
| | | 1ST to 7th floor | 2964.85 sq.mtrs. | Residential |
| | | 8th floor | 357.21 sq. mtrs. | Residential / Refuge Area |
| | | 9th to 11th floor | 1270.65 mtrs. | Residential |
| | 8 | Stilt | | Parking |
| | | 1ST to 7th floor | 2964.85 sq.mtrs. | Residential |
| | | 8th floor | 357.21 sq. mtrs. | Residential / Refuge Area |
| | | 9th to 11th floor | 1270.65 mtrs. | Residential |

On sub plot B

| No | Bldg.No | FLOOR | FLOOR AREA | OCCUPANCY |
|---|---|---|---|---|
| 1 | 3 | Stilt + 20th floor | | Parking |
| | | 1ST to 7th floor | 2179.59 sq.mtrs. | Residential |
| | | 8th, 13th ,18th floor | 623.58 sq. mtrs. | Residential / Refuge Area |
| | | 9th to 12th ,14th to 17th 19th & 20th floor | 3113.70 mtrs. | Residential |
| 2 | 5 | Stilt/ Gr.floor + 20th floor | 119.47 sq.mt | Parking/Shops |
| | | 1ST to 7th floor | 1577.10 sq.mt | Residential |
| | | 8th, 13th ,18th floor | 468.81sq.mt | Residential / Refuge Area |
| | | 9th to 12th ,14th to 17th 19th & 20th floor | 2253.00 sq.mt | Residential |
| 2 | 6 | Gr.floor + 20th floor | 393.99 sq.mt | Shops |
| | | 1ST to 7th floor | 2359.77sq.mt | Residential/1stfloor Shops |
| | | 8th, 13th ,18th floor | 675.87sq.mt | Residential / Refuge Area |
| | | 9th to 12th ,14th to 17th 19th & 20th floor | 3276.30 sq.mt | Residential |

**SUGGESTIONS :**

The fire brigade department has no objection for height of buildings, floor area and occupancy for the above mentioned buildings subject to the compliance of the conditions mention in this NOC.

**MEANS OF ESCAPE :**

- Two enclosed staircases having the width of 1.50 mt. are proposed in the building No.7, 8 on sub plot A and One enclosed staircase having the width of 1.50 mt. proposed in building No.3, 5, 6 on sub plot B.
- Treads and rises of each building are as per the existing building byelaws.

**SUGGESTIONS :**

1. Proposed enclose staircases of the bldg. shall be reached via ventilated lobby and shall have access through self closing doors at least half an hour of fire resistance.'
2. Doors shall be single swing door opening in the direction of escape.
3. The door shall be fitted with check action door closers.
4. Permanent vent at the top of equal 5% of cross sectional area of staircase shall be provided in the proposed buildings.
5. Open able sashes at each floor level with area equal to 15 % of cross sectional area of the enclosure on the external wall shall be provided.
6. Staircases of the proposed buildings must be well illuminated around the clock.
7. Lighting for the staircases of all the buildings must be connected to standby Electric supply.
8. Lifts shall not be used as a means of escape during emergency.
9. All the exits & directions of travel to exits must be conspicuously marked with the illuminated signs.

7) The vertical shaft for electric cables must be enclosed at each floor level with non combustible fire resistance enclosures of not less than two hours rating.

**ELECTRIC CABLE SHAFT & ELECTRIC METER BOARDS:**

**For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

1) Electric cable shafts shall be exclusively used for electric cables and shall not open in the staircase enclosure.
2) Electric meter rooms shall be adequately ventilated and preferably it should be away from staircases in a safe place.
3) Electric shafts shall be sealed at each floor level with non- combustible material such as vermiculite concrete.
4) Inspection door for the shaft if provided shall have two hours fire resistance.

**ALTERNATIVE SOURCE:** **For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

An alternative source of L.V./H.V supply from a separate sub-station with appropriate change over switch shall be provided for fire-pump, fire lift, staircase and corridor lighting circuit's manual fire alarm system and jocky pump. It shall be housed on/in separate cables. Apart from this en equal capacity D.G. sets shall be provided. It shall be installed as per C-1.15 of the provision of N.B.C part IV of 2005.

**ESCAPE ROUTE LIGHTING:** **For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Escape route lighting (Staircase and Corridor lights) shall be on independent circuits it should be comply the requirements as per rules i.e as per 4.6 of N.B.C Part IV-2005.

**LIGHTING CONDUCTOR:** **For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

It is proposed to protect the building against lighting by installing lighting protection system confirming to latest IS code of practice 2309. The lighting protection must be maintained in good repairs at all times. This should protect the building and light structure against lighting.

**FIRE FIGHTING REQUIREMENTS:**


**UNDERGROUND WATER STORAGE TANK:** **For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

An underground water storage tank of not less than 1,50,000 ltrs. capacity for buildings shall be provided. The said capacities of U.G. Tanks are exclusively for fire fighting and shall be provided at ground level as location marked on the plan. As per the design specified in the rules with battles walls and fire brigade collecting breaching. Underground tanks shall be connected to wet risers and courtyard hydrant system.

**OVERHEAD (TERRACE) WATER STORAGE TANK:**

**For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Another tank of 20,000 Ltrs. Capacity shall be provided at terrace level for building. The design and layout of this tank shall be got approved form concerned department prior to its erection. The tank shall be connected to wet riser through a booster pup through N.R valve and gate valve.



**WET RISER : For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

One wet-riser of internal diameter of 15.0 cms of G.I "C" class pipe shall be provided for building in the duct adjoining the staircase with twin hydrant outlet and hose reel on each floor in snitched in such a way as not to reduce the width of corridor. Pressure reducing discs or orifices shall be provided at lower level so as not to exceed pressure of 5.5 kgs/cm2. A fire service inlet on the external face of the building near the static tank directly fronting the courtyard shall be provided to connect the mobile pump of fire service to the wet riser.

**FIRE PUMP & BOOSTER PUMP: For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

a. Wet riser of each building shall be connected to a fire pump at ground level of capacity of not less than 3200 LPM capable of giving pressure of not less than 3.2 Kg/Cm2 at top most hydrant.
b. Booster pump of capacity 900 L.P.M. giving a pressure of not less than 5.2 kg/Cm2 t top most hydrant out let at the wet-riser shall be provided at the terrace level.
c. Testing of each pump with required pressure should be done with respect to the buildings & the pump set proposed for the building.
d. Electric supply (normal) to these pumps shall be on independent circuits.
e. Stand-by pump of equal capacity shall be provided.
f. No submergible pump will be allowed.

**EXTERNAL HYDRANTS : For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Minimum six external hydrants shall be provided for the proposed building within the confines of the site on the wet riser at locations marked on the plan.

**HOSE REEL :- For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Near each internal hydrant hose reel shall be installed. Each hose reel tubing terminating into shut-off nozzle of 5mm outlet. Hose reel shall be connected directly to the riser and it shall confirm to the latest codes 8092.

**HOSE BOXES: For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Hose boxes shall be provided in the proposed building on each floor near each internal hydrant and in the court yard Hydrant. Each box shall be equipped with 2 x 15m. length of rubber line hose along with standard branch pipe. It shall confirm to latest IS code 636 & 903 respectively.

**SPRINKLER SYSTEM: For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Common corridor, passage and lobby etc. of all the floors shall be protected by sprinklers of the propose building. Design of this sprinklers shall be as per latest IS specifications or approved by T.A.C./I.R.A.

**PORTABLE FIRE EXTINGUISHERS:- For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

The following portable extinguishers shall be provided at the electric meter room (service) at ground floor level/stilt and the lift machine room at terrace level,

i. D.C.P. type fire extinguishers of 5 kg capacity with ISI Marks – 1 No.
ii. Buckets filled with dry clean sand – 2 Nos.
iii. For each kitchen room there should be provision of portable extinguishers.

10. Bothe staircases shall be of enclosed type creating a disconnecting lobby from the lift areas on each floor.

11. Both the staircases shall be of pressurization type which will comply the requirement as per 4.10 at NBC part IV 2005

**MEANS OF ENTRY :**

- Three out of two lifts which are attached with each other, are proposed in building No.7,8 on sub plot A and two lifts which are attached with each other, are proposed in building No.3,5,6 on sub plot B.
- The lifts of the building are of high speed in nature.

**SUGGESTIONS :**

1. Planning & design of the lifts shall be accordance with latest national building code (NBC) (i.e. section 5, installation of lifts and escalators)
2. Lifts of the building are to be provided with automatic steel doors for lift cars & landings.
3. One lift in the BLDG. shall be designed and designated as fire lift.
4. This lift shall be equipped with fireman's switch for grounding it in the event of fire.
5. Walls of each lift enclosure shall have fire resistance of not less than 2 hours.
6. Landing doors in the lift enclosure shall have of not less than 1 hour.
7. Lift car doors shall have fire resistance of 2 hours.
8. Separating wall of 2 hours fire resistance shall be provided between the lift shafts.
9. Fire lift of the building shall be conspicuously painted with fluorescent paint on all landing doors of fire lift.
10. Fire lift of the building can however be used for other purposes under normal conditions.
11. A Disconnection lobby shall be provide to lift and lift lobby area by providing of fire resistant doors.
12. If should comply the requirements as per C- 1.5 of NBC part IV of 2005.

The fire lift of the buildings shall meet following requirements:-

1. It must be connected to stand by source of power supply.
2. It must be ensured that power cables to fire lift are laid along the route which is fire safe.
3. Power supply to fire lift must automatically trip over type to the alternate source power supply in the event of failure of normal power supply.

**REFUGE AREAS:**

Space for refuge area is to be kept in the propose building as per existing building. Bye laws. Area and side of the refuge areas of proposed buildings are as follows.
Refuge area 70.91 sq. mtrs. each is proposed on the 8th floor in each Building No.7 & 8 on sub plot A
Refuge Area 95.36 sq. mtrs., 69.00 sq. mtrs and 102.70 sq. mtrs are proposed on the 8th, 13th, 18th floor in Building No. 3, 5, 6 respectively on sub plot B which is proposed as

"REFUGE AREA" is adequate and location is also acceptable by the fire brigade department.

Additional suggestions for refuge area for all the buildings are as follows.

1. The layout of refuge area shall not be changed / modified at any time in future.
2. There shall not be any opening in to the refuge area from any portion of the occupied premises.
3. Refuge area shall be segregated by brick masonry partition wall of 9" thickness & access to the refuge area shall be gained through half an hour fire resistant self – closing door.
4. Lifts & or open type staircase shall not open in to refuge area.
5. Clear height of the refuge area below the beam/drop parade shall not be less than 1.8 mtrs.
6. The refuge area shall be ear-marked exclusively for the use of occupant as the temporary shelter and for the user of fire brigade dept. & any other organization dealing with fire or other emergencies when occurs in the bldg. & also for exercise/drills if conducted by the fire brigade department.
7. The refuge area shall not be allowed to be used for any other purposes & it shall be responsibility of the owner / occupier to maintain the same clean & free of encumbrances & encroachment at all times.

8) The entrance door to the refuge area shall be fire resistant and will be painted or fixed with a sign painted in luminous paint mentioning 'Refuge Area - in case of emergency.

9) Adequate drinking water facility shall be provided in the refuge area.

10) Adequate emergency lighting facility connected to the electric circuits of staircase, corridors / passage etc. lighting shall be provided.

**ELECTRIC INTALLATIONS:** **For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

The locations of the substations are marked on the plan and suggested that at the time of installation of sub-station/transformer a separate clearance to be taken from the Fire Brigade and M.S.E.B department. Electrical services of the building shall confirm to the provision of C.1.12 of the NBC Part IV of 2005.

**GENERAL RECOMMENDATIONS FROM THE POINT OF FIRE SAFETY FOR ELECTRICAL INSTALLATIONS ARE AS FOLLOWS:-**

**For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

1) The electric distribution cables/ wiring all the buildings shall be laid in separate duct.
2) The duct shall be sealed at every alternative floor with non-constructive material having the same fire resistance as that of the duct.
3) Water mains, telephone lines, inter-com lines or any other service line shall not be laid in the duct for electrical cables.
4) Separate circuits for water pumps, lifts, staircases and corridor lighting shall be provided directly from the main switch gear panel and these circuits shall be laid in separate conduit pipes so that fire in one circuit will not affect the others. Master switched controlling essential services circuits shall be clearly labeled.
5) Medium and low voltage wiring running if shaft and if it is in the false ceiling it shall run in metal conduct.
6) The electric sub-station and stand by generator room must be compartmentalized.

iv. Extinguishers shall be displayed at strategic locations in all the entire buildings as per latest I.S. 2190.

**FIRE ALARM SYSTEM:- For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Proposed residential building shall be provided with manual fire alarm system with main control panel at ground floor level and pill boxes and hooters at each of the upper floors levels. The layout of the fire alarm system shall be in accordance to the Indian Standards Specifications.

**FIRE CONTROL ROOM- For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Fire Control Room shall be proposed on the ground/stilt –floor level of building. The size of fire control room must be adequate for housing all indicating / control equipment for the fire alarm system, public address room.

**FIRE DIRECTION SYSTEM:- For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Entire building include meter room, D.G. Room Transformer room shall be protected. With automatic Detection System. Design of this system shall be as per latest I.S. 2189.

**SERVICE DUCTS: For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Service ducts which are proposed in the building should be enclosed by walls at least two hours fire resistance and should be sealed at every alternate floors with non combustible material having at least two hours fire resistance.

**FIRE DRILLS / FIRE ORDER: For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Fire notices & order shall be prepared to fulfill the requirements of firefighting and evacuation from the building in the of fire & other emergency.

The occupants shall be made thoroughly conversant with their actions in the event of emergency by displaying fire notices at vantage points & also through regular training such notices shall be displayed prominently in bold lettering.

**HOUSE KEEPING : For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

To eliminated fire Hazards good house keeping both inside & outside the building shall be strictly maintained by the occupants and / or owner of the building.

**HELIPAD : (ONLY FOR BUILDINGS WHICH IS MORE THAN 60.M)**
**For bldg. No. 7 & 8 on sub plot A**
**For bldg. No. 3, 5 & 6 on sub plot B**

Provision of Helipad shall be made in the propose building in consultation with other Govt.Dept.

**Capitation Fees and Scrutiny Fees –**

Party has paid the required Capitation fees and Scrutiny fees as under

On sub plot A Bldg. No. 7 & 8

**Capitation Fees:**

| Sr. No. | Building No. | Area (sq.mt) | Capitation Fee (Rs). | D.D.No. and Date | Receipt No. and Date |
|---|---|---|---|---|---|
| 1 | 7 | 6145.52 sq.mt | Rs. 3, 25, 000/- | D.D.No.025337 Date 11.06.2010 | 221047 Dt. 15.06.2010 FIR/HQ/000324/2010 |
| 2 | 8 | 6145.52 sq.mt | Rs. 3, 25, 000/- | D.D.No.025338 Date 11.06.2010 | 221049 Dt. 15.06.2010 FIR/HQ/000326/2010 |

**Scrutiny Fees:**

| Sr. No. | Building Type | Area (sq.mt) | Scrutiny Fee (Rs). | D.D.No. and Date | Receipt No. and Date |
|---|---|---|---|---|---|
| 1 | 7 | 6145.52 sq.mt | Rs. 1, 84, 380/- | D.D.No.025340 Date 11.06.2010 | 221048 Dt. 15.06.2010 FIR/HQ/000325/2010 |
| 2 | 8 | 6145.52 sq.mt | Rs. 1, 84, 380/- | D.D.No.025341 Date 11.06.2010 | 221050 Dt. 15.06.2010 FIR/HQ/000327/2010 |

On sub plot B Bldg. No. 3, 5, 6

**Capitation Fees:**

| Sr. No. | Building No. | Area (sq.mt) | Capitation Fee (Rs). | D.D.No. and Date | Receipt No. and Date |
|---|---|---|---|---|---|
| 1 | 3 | 5932.00 sq.mt | Rs. 3, 25, 000/- | D.D.No.025335 Date 11.06.2010 | 221041 Dt. 15.06.2010 FIR/HQ/000318/2010 |
| 2 | 5 | 6037.00 sq.mt | Rs. 3, 65, 000/- | D.D.No.025339 Date 11.06.2010 | 221043 Dt. 15.06.2010 FIR/HQ/000320/2010 |
| 3 | 6 | 7930.00 sq.mt | Rs. 4, 36, 500/- | D.D.No.025336 Date 11.06.2010 | 221045 Dt. 15.06.2010 FIR/HQ/000322/2010 |

**Scrutiny Fees:**

| Sr. No. | Building Type | Area (sq.mt) | Scrutiny Fee (Rs). | D.D.No. and Date | Receipt No. and Date |
|---|---|---|---|---|---|
| 1 | 3 | 5932.00 sq.mt | Rs. 1, 77, 960/- | D.D.No.025333 Date 11.06.2010 | 221042 Dt. 15.06.2010 FIR/HQ/000319/2010 |
| 2 | 5 | 6037.00 sq.mt | Rs. 2, 21, 110/- | D.D.No.025334 Date 11.06.2010 | 221044 Dt. 15.06.2010 FIR/HQ/000321/2010 |
| 3 | 6 | 7930.00 sq.mt | Rs. 2, 77, 900/- | D.D.No.025332 Date 11.06.2010 | 221046 Dt. 15.06.2010 FIR/HQ/000323/2010 |

T.D.O. department is requested to verify the total built-up area and inform this office if same is found to be more for the purpose of levying additional Capitation Fees, if required.

Thane Municipal Corporation of the City of Thane

**Chief Fire Officer**

**Thane Fire Bridge Thane.**