




**LODHA ACME OZONE THANE**

**WINDOWS SCHEDULE**

**TYPICAL FLOOR**

| Sr.No | WIN NO. | Location | Masonry Opening Width C | Masonry Opening Height D | Sill Height | Lintel Height |
|---|---|---|---|---|---|---|
| 1 | W1 | Bedroom | 2425 | 2175 | 125 | 2300 |
| 2 | W1A | Bedroom | AS PER STR. | 2175 | 125 | 2300 |
| 3 | W2 | Bedroom | 2100 | 2175 | 125 | 2300 |
| 4 | W3 | 4BHK Bedroom | 750 | 2175 | 125 | 2300 |
| 5 | W4 | Toilets | 750 | 1200 | 1100 | 2300 |
| 5 | W4A | Toilets | 750 | 1650 | 650 | 2300 |
| 6 | W5 | Toilets (TOWER - F - 2BHK ) | 675 | 1100 | 1200 | 2300 |
| 6 | W5A | Toilets (TOWER - F - 2BHK ) | 675 | 1650 | 650 | 2300 |
| 7 | W10 | Utility | 750 | 1650 | 650 | 2300 |
| 8 | SD11 | Living Room to Deck | 2425 | 2300 | N/A | 2300 |
| 9 | SD12 | Living Room to Deck (4BHK) | 4800 | 2300 | N/A | 2300 |
| | | **LIFT LOBBY** | | | | |
| 1 | W6 | Lift Lobby | 1800 | 2175 | 125 | 2300 |
| 2 | W7 | Fire Lift Lobby at Mid-Landing Level & Servant Room (Staircase-3) | 1200 | 2156 | 746 | 2900 |
| 3 | W7B | Fire Lift Lobby at Mid-Landing Level & Servant Room (Staircase-3) -TERRACE FLOOR | 1200 | 2156 | 646 | 2800 |
| 4 | W8 | Staircase 02 | 900 | 1100 | 1200 | 2300 |
| 5 | W9 | Lift Lobby | 750 | 2175 | 125 | 2300 |
| | | **AMENITY FLOOR** | | | | |
| 1 | W7A | Fire Lift Lobby at Mid-Landing Level & Servant Room (Staircase-3) | 1200 | 2156 | 920 | 3075 |
| 2 | SD13 | Living Room to Deck | 2425 | 2680 | N/A | 2680 |
| 3 | SD14 | Living Room to Deck | 2100 | 2680 | N/A | 2680 |
| 4 | CW | | | | | |

**LODHA ACME OZONE THANE**

**DOORS SCHEDULE**


**TYPICAL FLOOR**

| Sr.No | DOOR NO. | Location | Sill level | Lintel level | Masonary Width C | Masonary Height D |
|---|---|---|---|---|---|---|
| 1 | FD1 | Main Door / Refuge Floor Entrance | NA | 2300 | 1100 | 2300 |
| 2 | D2 | Bedrooms / Study / Servant Main Door @ Mid-Landing | NA | 2300 | 900 | 2300 |
| 3 | D3 | Toilet / Servant Toilet @ Passage | NA | 2300 | 800 | 2300 |
| 4 | FD4 | Kitchen | NA | 2300 | 900 | 2300 |
| 5 | D5 | Kitchen to Utility | NA | 2300 | 1100 | 2300 |
| 6 | D6 | Bedroom to Shaft | NA | 2300 | 750 | 2300 |
| | | **LIFT LOBBY** | | | | |
| 1 | FD10 | A1 Staircase | NA | 2300 | 1200 | 2250 |
| 2 | FD11 | ELEC/A.V. Duct/Plumbing Duct | 450 | 2300 | 900 | 1850 |
| 3 | FD12 | ELEC/A.V. Duct/Plumbing Duct | 450 | 2300 | 1200 | 1850 |
| 4 | FD13 | Fire Duct | 450 | 2300 | 900 | 1850 |
| 5 | FD14 | Fire Duct | 450 | 2300 | 1200 | 1850 |
| 6 | D3 (D7) | Servant Toilet @ Mid-Landing | NA | 2300 | 750 | 2300 |
| | | **AMENITY FLOOR** | | | | |
| 1 | D8 | Store room | NA | 2300 | 700 | 2300 |
| 2 | GD15 | Indoor games, Gym, Library, party hall | NA | 2300 | 1200 | 2300 |
| 3 | GD16 | Indoor games, Gym, Library, party hall | NA | 2300 | 1200 | 2300 |
| | | **GROUND FLOOR LEVEL** | | | | |
| 1 | FD9 | Meter room | | | 1050 | 2250 |
| 2 | FD9 | Letter Room | | | 1050 | 2250 |
| 3 | FD9 | Utility Duct | | | 750 | 1650 |
| | | **ROLLING SHUTTER** | | | | |
| 1 | RS01 | SHOP 01 | | | 1050 | 2250 |
| 2 | RS02 | SHOP 02 | | | | |
| 3 | RS03 | SHOP 03 | | | | |
| 4 | RS04 | SUBSTATION | | | | |
| 5 | RS05 | Service lift | | | | |
| 6 | RS06 | EXISTING PUMP ROOM | | | 1800 | |
| 7 | RS07 | PUMP ROOM | | | | |
| 8 | RS08 | EXISTING RETAIL ENTRY | | | | |

**LEGEND**

| FLOORS | LEVELS |
|---|---|
| ROOF | |
| OHT / LMR | |
| TERRACE | +222.40 |
| 35TH+ PENTHOUSE | +219.35 |
| 34TH+ PENTHOUSE | +216.30 |
| 33TH REFUGE | +213.25 |
| 32TH | +210.20 |
| 31TH | +207.15 |
| 30TH | +204.10 |
| 29TH | +201.05 |
| 28TH REFUGE | +198.00 |
| 27TH | +194.95 |
| 26TH | +191.90 |
| 25TH | +188.85 |
| 24TH | +185.80 |
| 23RD REFUGE | +182.75 |
| 22ND | +179.70 |
| 21ST | +176.65 |
| 20TH | +173.60 |
| 19TH | +170.55 |
| 18TH REFUGE | +167.50 |
| 17TH | +164.45 |
| 16TH | +161.40 |
| 15TH | +158.35 |
| 14TH | +155.30 |
| 13TH REFUGE | +152.25 |
| 12TH | +149.20 |
| 11TH | +146.15 |
| 10TH | +143.10 |
| 9TH | +140.05 |
| 8TH REFUGE | 137.00 |
| 7TH | +133.95 |
| 6TH | +130.90 |
| 5TH | +127.85 |
| 4TH | +124.80 |
| 3RD | +121.75 |
| 2ND | +118.70 |
| 1ST + TOWNHOUSE | +115.65 |
| STILT + TOWNHOUSE | +112.25 |
| P3 | +108.60 |
| P2 | +105.80 |
| P1 | +103.00 |
| GROUND | +100.00 |
| BASEMENT 01 | +097.15 |
| BASEMENT 02 | +094.30 |

KEY SECTION




KEY PLAN

GENERAL NOTES

1 : All dimensions are in millimeters and levels in meters unless specified otherwise.
2 : Do not scale the drawing; follow written dimensions.
3 : All dimensions are unfinished dimensions unless specified otherwise.
4 : Any discrepancies should be brought to the notice of the Architect prior to execution of job / procuring materials at site.
5 : This drawing is the property of Kapadia Associates and should not be reproduced, copied, handed over to a third party or used for any purpose other than for which it has been issued.
6 : This drawing is to be read in conjunction with all relevant structural & services drawings.

REVISION INDEX

| REV. NO. | DATE | REMARKS |
|---|---|---|
| R00 | 29-06-2023 | VFC ISSUED |
| | | |
| | | |
| | | |
| | | |
| | | |

CLIENT

**LODHA**

PROJECT TITLE

**L-13722 LODHA BELLA VISTA**

THANE

DRAWING TITLE & NO.

**BS-311_SECTION 02 & 03**

DRAWING STAGE

**WORKING DRAWING**

| SCALE | REV. NO. | REV. DATE |
|---|---|---|
| 1:75 | R00 | 29-06-2023 |

STAMP & SIGNATURE

N


KAPADIA ASSOCIATES
architecture • urban design
112-114, Peninsula Centre,Dr. S.S. Rao Road,Parel East, Mumbai 400012
Tel : 91-22-6660 2838 / 39 E-mail : kapl@kapl.in Website : www.kapl.in