दुरध्वनी : २५३३ १२११
२५३३ १५९०

ठाणे महानगरपालिका

महानगरपालिका भवन, डॉ. अल्मेडा रोड, चंदनवाडी, पाचपाखाडी, ठाणे-४०० ६०२.
THE MUNICIPAL CORPORATION OF THE CITY OF THANE

संदर्भ क्र./ठा.म.पा./ दिनांक / / २००
Ref./T.M.C./ C.F.O/M/2410/125 Date 15/12/2012

To,
The Asst. Director of Town Planning
Thane Municipal Corporation,
Thane

Sub: Grant of N.O.C. stipulating, Fire Protection & Fire Fighting requirements for the proposed MMRDA building no. 1, 2, 5 & 6 on land bearing Gut No. **61/1/1, 2, 3, 4, 61/2/1, 2, 3** at Village Chitalsar(Manpada) Tal & Dist, Thane.
For Ascent Construction Pvt. Ltd. Through Director Shri.Pravin H. Doshi

Re: i. A letter from an Architect Shri. Subhash Gupte dt. 19/10/2012.
ii. V.P. No. 88/142.
iii. Site Visit 04/12/2012.

Dear Sir,

Proposal is to construct the Residential building on Gut No. **61/1/1, 2, 3, 4, 61/2/1, 2, 3** at Village Chitalsar Manpada Tal & Dist, Thane.

The architectural plans of proposed buildings are referred to the Chief Fire Officer, Thane Fire Brigade, Thane by an Architect **Shri. Subhash Gupte, Gupte College, Opp. Bhakti Mandir, Panchpakhadi, Thane (W) 400 602.** The plans of these buildings are scrutinized by this department as per existing buildings by-laws from the point of fire safety and means of escape.

Observations and Directives of Chief Fire Officer, Thane Fire Brigade, Thane for the said proposal are given below.

OBSERVATIONS & DIRECTIVES

A) Plot under reference is 44133.20 m2 in area.

B) The said plot is sub divided in to sub plot A & sub plot B by 20.m. wide existing D.P.Road.

C) Total 18 buildings are proposed on the above reffered plot.

D) Out of 18 buildings 8 buildings are proposed on sub plot A & 8 buildings are proposed on sub plot B.

E) Architect has submitted plans of 4 buildings namely MMRDA building No. 1, 2, 5 & 6 in sub plot B.

F) Architectural plans of above 04 buildings are scrutinized by this department as per existing building by laws & remarks are attach here with.

Building no. MMRDA building No. 1, 2, 5 & 6

G) MMRDA Building No. 1, 2, 5 & 6 are proposed on the sub plot B.

H) Sub plot B is approachable by 20m. wide existing D.P. Road from south side.

Thane Municipal Corporation for the City of Thane
ठाणे महानगर पालिका
अग्निशमन दल
Fire Brigade Dept.

I) All the 4 buildings i.e. MMRDA building No. 1, 2, 5 & 6 are approachable by 10.0 m. wide propose road from west side & 20.00 mt. wide propose road from south side.

J) Adequate open spaces are proposed on the ground floor for all the 4 buildings.

K) Propose MMRDA bldg. no. 1 is Gr. + 25th flr. i.e. 76.30 mt. , MMRDA bldg. no. 2 is St. + 24th flr. i.e. 73.40 mt. , MMRDA bldg. no. 5 is St. + 22nd flr. i.e. 67.60 mt. MMRDA bldg. no. 6 is St./Gr. + 22nd flr. i.e. 67.60 mt. in height from ground level.

L) Stilt floor of bldg. no. 2 & Part stilt floor for bldg. no. 6 will be use exclusively for parking & remaining all the floors will be use for residential & commercial purposes.

M) All buildings are two enclose staircase having the width of 1.5 m. is proposed in each building.

N) Two lifts are propose in bldg. no. 5 & other 3 buildings four lifts are propose in each building. Both the lift of each buildings are attached with each other.

O) Required space for refuse area is kept on 8th, 13th & 18th , 23rd floor of bldg. no. 1 & 2, & bldg. no. 5 & 6 for refuse area kept on 8th, 13th, & 18th floors.

P) Locations of meter room, substation & D.G. set is not marked on the plan for any building.

Q) Required firefighting measures are not marked on the plan for any building.

Considering the above situation following fire prevention and protection measures are recommended in all the 4 buildings i.e. in bldg. no. 1, 2, 5 & 6 which are proposed on sub plot B.

MAIN ROAD/D.P. ROAD. :

Sub plot B is approachable by 20.0 m. wide Existing road from south side and 10.0m. wide D.P. road from west side. the proposed building i. e.1, 2, 5 & 6 are approachable from the said road.

SUGGESTIONS :

No additional suggestions are given by this dept. neither for main road nor for internal road.

OPEN SPACE :-

Open space around proposed high rise Residential building is as follows:

		OPEN SPACE			
		Sub plot B			
S.No.	Side	Bldg. No.1	Bldg. No. 2	Bldg. No. 5	Bldg. No. 6
1	North	7.50 mt	7.50 mt	6.00 mt	6.00 mt
2	South	6.00 mt	7.50 mt	10.40 mt	7.60 mt
3	East	6.00 mt	6.00 mt	7.50 mt	7.50 mt
4	West	8.00 mt.	8.00 mt	7.50 mt	12.00 mt

SUGGESTIONS :

i. Minimum 6.0 mtr. Open space around the bldg. must be maintained free of all encroachment / obstructions / parking for the easy movement of fire appliances and same shall be capable of taking the load of fire engine upto 45.0 tone.

ii. Parking shall not be allowed in the driveway.

iii. Open spaces shall be paved from all the sides.

iv. UG Tank shall not be proposed in the minimum required open spaces.

v. Turning circle radius on any corner shall not be less than 10.0 meter.

ENTRY GATES :

1. Two gates are proposed for the entire sub plot B, which are on the west & south side.

SUGGESTIONS :

1. Minimum 1 entry gate and 1 exit shall be provided for the proposed high rise residential buildings.
2. Entry gates shall be located preferably attached to the approach Roads.
3. The width and hight clearance of the entry gate shall not be less than 5 mtrs.

HEIGHT , FLOOR AREA & OCCUPANCY :

The height and built-up are & occupancy of each building are as follows :

On sub plot B

No	Bldg.No	FLOOR	FLOOR AREA	OCCUPANCY
1	1	Gr. & 1st floor	479.98 sq.mtrs.	Commercial
		2nd to 7th floor	2196.39 sq. mtrs.	Residential
		8th, 13th ,18th , 23rd floor	9060.28 mtrs.	Residential / Refuge Area
		9th to 12th ,14th to 17th 19th to 22nd, 23rd to 25th floor	4392.78	Residential
2	2	Stilt + 24th floor	--	Parking
		1st floor	244.49 sq.mt	Amenities
		2nd to 7th floor	1496.64 sq.mt	Residential
		8th, 13th ,18th , 23rd floor	769.28 sq.mt	Residential / Refuge Area
		9th to 12th ,14th to 17th 19th &22nd & 24th floor	3178.37 sq.mt	Residential
3	5	St. + 22nd floor	--	Parking
		1ST to 7th floor	1729.16 sq.mt	Residential/
		8th, 13th ,18th floor	581.40 sq.mt	Residential / Refuge Area
		9th to 12th ,14th to 17th 19th & 22nd floor	2962.56 sq.mt	Residential
4	6	Gr./St. + 22nd floor	291.15 sq.mt	Shops
		1ST to 7th , 9th to 12th, 14th to 17th, 19th to 22nd	8367.98 sq.mt	Residential/
		8th, 13th ,18th floor	1059.48 sq.mt	Residential / Refuge Area

SUGGESTIONS :

The fire brigade department has no objection for height of buildings, floor area and occupancy for the above mentioned buildings subject to the compliance of the conditions mention in this NOC.

MEANS OF ESCAPE :

Two enclosed staircase having the width of 1.50 mt. proposed in building No. 1, 2, 5 & 6 on sub plot B.

Treads and rises of each building are as per the existing building byelaws.

Thane Municipal Corporation ठाणे महानगर पालिका अग्निशमन दल Fire Brigade Dept.

SUGGESTIONS :

1. Proposed enclose staircases of the bldg. shall be reached via ventilated lobby and shall have access through self closing doors at least half an hour of fire resistance.'
2. Doors shall be single swing door opening in the direction of escape.
3. The door shall be fitted with check action door closers.
4. Permanent vent at the top of equal 5% of cross sectional area of staircase shall be provided in the proposed buildings.
5. Open able sashes at each floor level with area equal to 15 % of cross sectional area of the enclosure on the external wall shall be provided.
6. Staircases of the proposed buildings must be well illuminated around the clock.
7. Lighting for the staircases of all the buildings must be connected to standby Electric supply.
8. Lifts shall not be used as a means of escape during emergency.
9. All the exits & directions of travel to exits must be conspicuously marked with the illuminated signs.
10. Bothe staircases shall be of enclosed type creating a disconnecting lobby from the lift areas on each floor.
11. Both the staircases shall be of pressurization type which will comply the requirement as per 4.10 at NBC part IV 2005

MEANS OF ENTRY :

- Four out of two lifts which are attached with each other, are proposed in building No.1, 2, 5 & 6 on sub plot B and two lifts which are attached with each other, in building No.5.
- The lifts of the building are of high speed in nature.

SUGGESTIONS :

1. Planning & design of the lifts shall be accordance with latest national building code (NBC) (i.e. section 5, installation of lifts and escalators)
2. Lifts of the building are to be provided with automatic steel doors for lift cars & landings.
3. One lift in the BLDG. shall be designed and designated as fire lift.
4. This lift shall be equipped with fireman's switch for grounding it in the event of fire.
5. Walls of each lift enclosure shall have fire resistance of not less than 2 hours.
6. Landing doors in the lift enclosure shall have of not less than 1 hour.
7. Lift car doors shall have fire resistance of 2 hours.
8. Separating wall of 2 hours fire resistance shall be provided between the lift shafts.
9. Fire lift of the building shall be conspicuously painted with fluorescent paint on all landing doors of fire lift.

10. Fire lift of the building can however be used for other purposes under normal conditions.

11. A Disconnection lobby shall be provide to lift and lift lobby area by providing of fire resistant doors.

12. If should comply the requirements as per C- 1.5 of NBC part IV of 2005.

The fire lift of the buildings shall meet following requirements:-

1. It must be connected to stand by source of power supply.

2. It must be ensured that power cables to fire lift are laid along the route which is fire safe.

3. Power supply to fire lift must automatically trip over type to the alternate source power supply in the event of failure of normal power supply.

REFUGE AREAS:

Refuge Area 95.95 sq. mtrs., 74.84 sq. mtrs and 53.00 sq. mtrs & 95.00 sq.mtrs. are proposed on the 8th, 13th, 18th , 23rd floors floor in Building No. 1, 2, 5 & 6 respectively on sub plot B which is proposed as "REFUGE AREA" is adequate and location is also acceptable by the fire brigade department

Additional suggestions for refuge area for all the buildings are as follows.

1. The layout of refuge area shall not be changed / modified at any time in future.

2. There shall not be any opening in to the refuge area from any portion of the occupied premises.

3. Refuge area shall be segregated by brick masonry partition wall of 9" thickness & access to the refuge area shall be gained through half an hour fire resistant self – closing door.

4. Lifts & or open type staircase shall not open in to refuge area.

5. Clear height of the refuge area below the beam/drop parade shall not be less than 1.8 mtrs.

6. The refuge area shall be ear-marked exclusively for the use of occupant as the temporary shelter and for the user of fire brigade dept. & any other organization dealing with fire or other emergencies when occurs in the bldg. & also for exercise/drills if conducted by the fire brigade department.

7. The refuge area shall not be allowed to be used for any other purposes & it shall be responsibility of the owner / occupier to maintain the same clean & free of encumbrances & encroachment at all times.

8) The entrance door to the refuge area shall be fire resistant and will be painted or fixed with a sign painted in luminous paint mentioning 'Refuge Area - in case of emergency.

9) Adequate drinking water facility shall be provided in the refuge area.

10) Adequate emergency lighting facility connected to the electric circuits of staircase, corridors / passage etc. lighting shall be provided.

ELECTRIC INTALLATIONS: For bldg. No. 1, 2, 5 & 6 on sub plot B

The locations of the substations are marked on the plan and suggested that at the time of installation of sub-station/transformer a separate clearance to be taken from the Fire Brigade and M.S.E.B department. Electrical services of the building shall confirm to the provision of C.1.12 of the NBC Part IV of 2005.

Thane Municipal Corporation of the City
ठाणे महानगर पालिका
अग्निशमन दल
Fire Brigade Dept.

GENERAL RECOMMENDATIONS FROM THE POINT OF FIRE SAFETY FOR ELECTRICAL INSTALLATIONS ARE AS FOLLOWS:-

For bldg. No. 1, 2, 5 & 6 on sub plot B

1) The electric distribution cables/ wiring all the buildings shall be laid in separate duct.
2) The duct shall be sealed at every alternative floor with non-constructive material having the same fire resistance as that of the duct.
3) Water mains, telephone lines, inter-com lines or any other service line shall not be laid in the duct for electrical cables.
4) Separate circuits for water pumps, lifts, staircases and corridor lighting shall be provided directly from the main switch gear panel and these circuits shall be laid in separate conduit pipes so that fire in one circuit will not affect the others. Master switched controlling essential services circuits shall be clearly labeled.
5) Medium and low voltage wiring running if shaft and if it is in the false ceiling it shall run in metal conduct.
6) The electric sub-station and stand by generator room must be compartmentalized.
7) The vertical shaft for electric cables must be enclosed at each floor level with non combustible fire resistance enclosures of not less than two hours rating.

ELECTRIC CABLE SHAFT & ELECTRIC METER BOARDS:

For bldg. No. 1, 2, 5 & 6 on sub plot B

1) Electric cable shafts shall be exclusively used for electric cables and shall not open in the staircase enclosure.
2) Electric meter rooms shall be adequately ventilated and preferably it should be away from staircases in a safe place.
3) Electric shafts shall be sealed at each floor level with non- combustible material such as vermiculite concrete.
4) Inspection door for the shaft if provided shall have two hours fire resistance.

ALTERNATIVE SOURCE: For bldg. No. 1, 2, 5 & 6 on sub plot B

An alternative source of L.V./H.V supply from a separate sub-station with appropriate change over switch shall be provided for fire-pump, fire lift, staircase and corridor lighting circuit's manual fire alarm system and jocky pump. It shall be housed on/in separate cables. Apart from this en equal capacity D.G. sets shall be provided. It shall be installed as per C-1.15 of the provision of N.B.C part IV of 2005.

ESCAPE ROUTE LIGHTING: For bldg. No. 1, 2, 5 & 6 on sub plot B

Escape route lighting (Staircase and Corridor lights) shall be on independent circuits it should be comply the requirements as per rules i.e as per 4.6 of N.B.C Part IV-2005.

LIGHTING CONDUCTOR: For bldg. No. 1, 2, 5 & 6 on sub plot B

It is proposed to protect the building against lighting by installing lighting protection system confirming to latest IS code of practice 2309. The lighting protection must be maintained in good repairs at all times. This should protect the building and light structure against lighting.

FIRE FIGHTING REQUIREMENTS:
UNDERGROUND WATER STORAGE TANK: For bldg. No. 1, 2, 5 & 6 on sub plot B

An underground water storage tank of not less than 1,00,000 ltrs. capacity for each buildings Shall be provided. The said capacities of U.G. Tanks are exclusively for fire fighting and shall be provided at ground level as location marked on the plan. As per the design specified in the rules with battles walls and fire brigade collecting breaching. Underground tanks shall be connected to wet risers and courtyard hydrant system.

OVERHEAD (TERRACE) WATER STORAGE TANK:

For bldg. No. 1, 2, 5 & 6 on sub plot B

Another tank of 20,000 Ltrs. Capacity shall be provided at terrace level for building. The design and layout of this tank shall be got approved form concerned department prior to its erection. The tank shall be connected to wet riser through a booster pup through N.R valve and gate valve.

WET RISER : For bldg. No. 1, 2, 5 & 6 on sub plot B

One wet-riser of internal diameter of 15.0 cms of G.I "C" class pipe shall be provided for building in the duct adjoining the staircase with twin hydrant outlet and hose reel on each floor in snitched in such a way as not to reduce the width of corridor. Pressure reducing discs or orifices shall be provided at lower level so as not to exceed pressure of 5.5 kgs/cm2. A fire service inlet on the external face of the building near the static tank directly fronting the courtyard shall be provided to connect the mobile pump of fire service to the wet riser.

FIRE PUMP & BOOSTER PUMP: For bldg. No. 1, 2, 5 & 6 on sub plot B

a. Wet riser of each building shall be connected to a fire pump at ground level of capacity of not less than 3200 LPM capable of giving pressure of not less than 3.2 Kg/Cm2 at top most hydrant.
b. Booster pump of capacity 900 L.P.M. giving a pressure of not less than 5.2 kg/Cm2 t top most hydrant out let at the wet-riser shall be provided at the terrace level.
c. Testing of each pump with required pressure should be done with respect to the buildings & the pump set proposed for the building.
d. Electric supply (normal) to these pumps shall be on independent circuits.
e. Stand-by pump of equal capacity shall be provided.
f. No submergible pump will be allowed.

EXTERNAL HYDRANTS : For bldg. No. 1, 2, 5 & 6 on sub plot B

Minimum six external hydrants shall be provided for the proposed building within the confines of the site on the wet riser at locations marked on the plan.

HOSE REEL :- For bldg. No. 1, 2, 5 & 6 on sub plot B

Near each internal hydrant hose reel shall be installed. Each hose reel tubing terminating into shut-off nozzle of 5mm outlet. Hose reel shall be connected directly to the riser and it shall confirm to the latest codes 8092.

HOSE BOXES: For bldg. No. 1, 2, 5 & 6 on sub plot B

Hose boxes shall be provided in the proposed building on each floor near each internal hydrant and in the court yard Hydrant. Each box shall be equipped with 2 x 15m. length of rubber line hose along with standard branch pipe. It shall confirm to latest IS code 636 & 903 respectively.

SPRINKLER SYSTEM: For bldg. No. 1, 2, 5 & 6 on sub plot B

Common corridor, passage and lobby etc. of all the floors shall be protected by sprinklers of the propose building. Design of this sprinklers shall be as per latest IS specifications or approved by T.A.C./I.R.A.

PORTABLE FIRE EXTINGUISHERS:- For bldg. No. 1, 2, 5 & 6 on sub plot B

The following portable extinguishers shall be provided at the electric meter room (service) at ground floor level/stilt and the lift machine room at terrace level,

i. D.C.P. type fire extinguishers of 5 kg capacity with ISI Marks – 1 No.
ii. Buckets filled with dry clean sand – 2 Nos.
iii. For each kitchen room there should be provision of portable extinguishers.
iv. Extinguishers shall be displayed at strategic locations in all the entire buildings as per latest I.S. 2190.

Thane Municipal Corporation of the City of Thane
ठाणे महानगर पालिका
अग्निशमन दल
Fire Brigade Dept.

FIRE ALARM SYSTEM:- For bldg. No. 1, 2, 5 & 6 on sub plot B

Proposed residential building shall be provided with manual fire alarm system with main control panel at ground floor level and pill boxes and hooters at each of the upper floors levels. The layout of the fire alarm system shall be in accordance to the Indian Standards Specifications.

FIRE CONTROL ROOM- For bldg. No. 1, 2, 5 & 6 on sub plot B

Fire Control Room shall be proposed on the ground/stilt –floor level of building. The size of fire control room must be adequate for housing all indicating / control equipment for the fire alarm system, public address room.

FIRE DIRECTION SYSTEM:- For bldg. No. 1, 2, 5 & 6 on sub plot B
Entire building include meter room, D.G. Room Transformer room shall be protected. With automatic Detection System. Design of this system shall be as per latest I.S. 2189.

SERVICE DUCTS: For bldg. No. 1, 2, 5 & 6 on sub plot B
Service ducts which are proposed in the building should be enclosed by walls at least two hours fire resistance and should be sealed at every alternate floors with non combustible material having at least two hours fire resistance.

FIRE DRILLS / FIRE ORDER: For bldg. No. 1, 2, 5 & 6 on sub plot B

Fire notices & order shall be prepared to fulfill the requirements of firefighting and evacuation from the building in the of fire & other emergency.
The occupants shall be made thoroughly conversant with their actions in the event of emergency by displaying fire notices at vantage points & also through regular training such notices shall be displayed prominently in bold lettering.

HOUSE KEEPING : For bldg. No. 1, 2, 5 & 6 on sub plot B
To eliminated fire Hazards good house keeping both inside & outside the building shall be strictly maintained by the occupants and / or owner of the building.

महाराष्ट्र आग प्रतिबंधक व जीव संरक्षक अधिनियम २००६ राज्यात लागू झाला आहे. इमारतीत किंवा तिच्या भागात आग प्रतिबंधक व जीव संरक्षक उपाययोजनांची तरतूद करण्यांकरता व सदरच्या उपाययोजना दुरुस्त आणि कार्यक्षम स्थितीत ठेवण्यासाठी, उपरोक्त अधिनियमातील कलम ३ चे (३) तसेच कलम ९ मध्ये "लायसन्सप्राप्त अभिकरणांची" तरतूद करण्यात आली आहे.

उपरोक्त अधिनियमातील तसेच तद्अनुषंगाने तयार करण्यात आलेल्या नियमांतील कार्यपध्दतीचा अवलंब करुन, ठाणे महापालिका हद्दीत असलेल्या इमारतीतील किंवा त्यांचे भागातील, आग प्रतिबंधक उपाययोजनांच्या अनुपालनासंबंधी "लायसन्सप्राप्त अभिकरण" म्हणून कार्य करण्यांकरीता महापालिकेच्या अग्निशमन विभागातर्फे काही व्यक्तीस तसेच व्यक्तींच्या संघास "लायसन्सप्राप्त अभिकरण" म्हणून घोषित करण्यात आले असून, त्यांची यादी अग्निशमन दलाच्या नोटीस बोर्डावर लावण्यात आली आहे. सबब, महाराष्ट्र आग प्रतिबंधक व जीव संरक्षक अधिनियम २००६ च्या तरतूदीनुसार "लायसन्सप्राप्त अभिकरण" म्हणून घोषीत करण्यात आलेल्या व्यक्ती किंवा व्यक्तींच्या संघाकडूनच इमारतीतील किंवा त्याच्या भागातील आग प्रतिबंधक व जीव संरक्षक उपाययोजनांच्या अनुपालनासंबंधी कामे करुन घेण्यांत यावी. व त्याबाबतचा विहित नमुन्यातील दाखला वापर परवाना मागतेवेळी सादर करण्यात यावा.

सन २०११-२०१२ ह्या आर्थिक वर्षात नविन दर प्रस्तावित करण्यात आले आहेत. अस्तित्वात असलेले दर व प्रस्तावित दरामधील फरक वास्तू विशारद / विकासक ह्यांना भरावयाच्या अटीवर सदरची फि जुन्या दराने स्विकारण्यात आली आहे.

CAPITATION FEES AND SCRUTINY FEES –

Party has paid the required Capitation fees and Scrutiny fees as under
Capitation Fees: On sub plot B Bldg. No. 1, 2, 5 & 6.

Sr. No.	Bldg. No.	Area (sq.mt)	Capitation Fee (Rs).	D.D.No. and Date	Receipt No. and Date
1	1	11586.00 sq.mt	Rs. 6, 95, 160/-	D.D.No.034431 Date 29.11.2012	0320352 Dt. 13.12.2012 FIR/HQ/001008/2012
2	2	8607.00 sq.mt	Rs. 5, 16, 420/-	D.D.No.034430 Date 29.11.2012	0320256 Dt. 13.12.202 FIR/HQ/001010/2012
3	5	7596.00 sq.mt	Rs. 4,55,760/- Already paid = Rs. 4,36,500/- FIR/HQ/000322/2010 Dt. 15/06/2010 Already paid = Rs. 1,17,862/- FIR/HQ/000910/2010 Dt.17/01/2011 Total paid = Rs. 5,54,362/-		--
4	6	13086.00 sq.mt	Rs. 7, 85, 160	D.D.No.034429 Date 29.11.2012	0320258 Dt. 13.12.202 FIR/HQ/001012/2012

Scrutiny Fees:

Sr. No.	Building Type	Area (sq.mt)	Scrutiny Fee (Rs).	D.D.No. and Date	Receipt No. and Date
1	1	11586.00 sq.mt	Rs. 3, 97, 580/-	D.D.No.034425 Date 29/11/2012	0320351 Dt. 13.12.2012 FIR/HQ/001007/2012
2	2	8607.00 sq.mt	Rs. 2, 58, 210/-	D.D.No.034426 Date 29.11.2012	0320354 Dt. 13.12.2012 FIR/HQ/001009/2012
3	5	7596.00 sq.mt	Rs. 2, 27, 880/-	D.D.No.034432 Date 29.11.2012	0320359 Dt. 13.12.2012 FIR/HQ/001013/2012
4	6	13086.00 sq.mt	Rs. 4, 42, 580/-	D.D.No.025332 Date 11.06.2010	0320351Dt. 13.12.2012 FIR/HQ/001007/2012

T.D.O. department is requested to verify the total built-up area and inform this office if same is found to be more for the purpose of levying additional Capitation Fees, if required.

Thane Municipal Corporation of the City of Thane ★ ठाणे महानगर पालिका ★ अग्निशमन दल ★ Fire Brigade Dept.

Chief Fire Officer
Thane Fire Bridge Thane.