

PALAVALAKEFRONT - SERENITY

TOWNHOUSE - FIRST FLOOR

ASPI - WING D

SR.NO	SR.NO	POINT CONTROL	MODULES	HT. OF SB (BTM OF SB FROM FL)	REMARKS
PUJA AREA					
L-01	1	CL - 1	1	1250MM	
FAMILY SPACE					
L-02	1	CL-2	1		
	2	6-A ,2 SOCKETS WITH 2 SWITCH	6	600MM	TO BE PLACED IN 2 ROWS OF 6/8 MODULE BOARDS INSTEAD OF ONE LARGE 10/12
	3	AC (SWITCH)	2		
L-03	1	BL-1	1		
	2	CL-3	1	600MM	
	3	CL-4	1		
	4	F-2 (ONLY REGULATOR)	2		
L-04	1	20A A.C BACK BOX	2	+250MM FROM BEAM BOTTOM[850 BEAM DEPTH]	
L-05	1	TV POINT	1	600MM	
	2	6-A , 1 SOCKET WITH 1 SWITCH	5		STB + TV ON SINGLE SWITCH [REFER KEY ELEVATION]
L-05A	1	6-A TV SOCKET	1	850MM	
PASSAGE					
P-01	1	CL-9	1	1250MM	
	2	CL-10	1		
	3	VDP		1500MM	
STORE ROOM					
S0.1	1	BL-4	1	1250MM	
BEDROOM-02					
B2-01	1	CL-5	1	1250MM	
	2	CL-6	1		
	3	F-3 (ONLY REGULATOR)	2		
	4	6-A SOCKET WITH SWITCH	3		
B2-02	1	TV POINT	1	600MM	
	2	6-A , 1 SOCKET WITH 1 SWITCH	5		
B2-02A	1	6-A TV SOCKET		850MM	
B2-03	1	20A A.C BACK BOX	2	+250MM FROM BEAM BOTTOM[850 BEAM DEPTH]	
B2-04	1	CL-7	1	600MM	
	2	CL-8	1		
	4	6-A SOCKET WITH SWITCH	3		
	5	AC (SWITCH)	2		
TOILET-02					
T2-01	1	BL-2	1	1250MM	
	2	BL-3 / EXHAUST FAN	1		
	3	GEYSER (SWITCH WITH INDICATOR)	1		
	5	6-A SOCKET WITH SWITCH	3		
T2-02	1	20 A SOCKET FOR GEYSER	2	2600MM	STORAGE GEYSER ABOVE FALSE CEILING
BEDROOM-03					
B3-01	1	CL-12 (2 WAY IN B3-03)	1	1250MM	
B3-02	1	TV POINT	1	600MM	
	2	6-A , 1 SOCKET WITH 1 SWITCH	5		STB + TV ON SINGLE SWITCH [REFER KEY ELEVATION]
B3-02A	1	6-A TV SOCKET		850MM	
B3-03	1	F-4 (ONLY REGULATOR)	2	600MM	
	2	CL-11	1		
	3	CL-12 (2 WAY IN B3-01)	1		
	3	6-A SOCKET WITH SWITCH	3		
B3-04	1	CL-13	1	600MM	
	2	CL-14	1		
	4	6-A SOCKET WITH SWITCH	3		
	5	AC (SWITCH)	2		
B3-05	1	20A A.C BACK BOX	2	+250MM FROM BEAM BOTTOM[850 BEAM DEPTH]	
TOILET-03					
T3-01	1	BL-7	1	1250MM	
	2	BL-8 / EXHAUST FAN	1		
	3	GEYSER (SWITCH WITH INDICATOR)	1		
	5	6-A SOCKET WITH SWITCH	3		
T3-02	1	20 A SOCKET FOR GEYSER	2	2600MM	STORAGE GEYSER ABOVE FALSE CEILING
BEDROOM - 04					
B4-01	1	CL-15 (2 WAY IN B4-02)	1	1250MM	
B4-02	1	CL-15 (2 WAY IN B4-01)	1	600MM	
	2	CL-16	1		
	3	CL-17	1		
	3	6-A SOCKET WITH SWITCH	3		
	4	F-5 (ONLY REGULATOR)	2		
B4-03	1	CL-18			
	2	CL-19	1	600MM	
	5	6-A SOCKET WITH SWITCH	3		
	6	AC(SWITCH)	2		
B4-04	1	TV POINT	1	600MM	
	2	6-A , 1 SOCKET WITH 1 SWITCH	5		STB + TV ON SINGLE SWITCH [REFER KEY ELEVATION]
B4-04A	1	6-A TV SOCKET		850MM	
B4-05	1	20A A.C BACK BOX	2	+250MM FROM BEAM BOTTOM[850 BEAM DEPTH]	
TOILET-04					
T4-01	1	BL-5	1	1250MM	
	2	BL-6 / EXHAUST FAN	1		
	3	GEYSER (SWITCH WITH INDICATOR)	1		
	5	6-A SOCKET WITH SWITCH	3		
T4-02	1	20 A SOCKET FOR GEYSER	2	2600MM	STORAGE GEYSER ABOVE FALSE CEILING

PALAVALAKEFRONT - SERENITY ASPI WING D

FIRST FLOOR - 3BHK UNIT (ROOM NO. 101)

SR.NO	SR.NO	POINT CONTROL	MODULES	HT. OF SB (BTM OF SB FROM SL)	REMARKS
ENTRANCE FOYER					
L-01	1	VDP BOX	1	1450MM	
POWER & ELV DB				1900MM (TOP OF DB)	
LIVING DINING					
L-02	1	CL-1 (2 WAY @L-05)	1	1250MM	
L-03	1	CL-04	1		
	2	6-A SOCKET WITH SWITCH	3		
	3	F-2 (REGULATOR)	2	1250MM	
	4	BL-01	1		
	5	AC (SWITCH)	1		
L-04	1	20A A/C BLACK BOX	2	2700MM	
L-05	1	CL-03	1		
	2	F-1 (REGULATOR)	2		
	3	CL-01 (2 WAY @ L-02)	1	600MM	TO BE PLACED IN 2 ROWS OF 6/8 MODULE BOARDS INSTEAD OF ONE LARGE 10/12 MODULE SQUARE BOX
	4	CL-02	1		
	5	6A SOCKET WITH SWITCH	3		
	6	BL-11	1		
	7	TELEPHONE POINT	1		
L-06	1	TV	1		
	2	DATA	1	600MM	
	3	6A 3 SOCKETS WITH 1 SWITCH	7		
PASSAGE					
P-01		CL-07	1	1250MM	
VDP	1	VDP BOX	2	1500MM	
KITCHEN					
K-01	1	CL-05	1		
	2	CL-06	1		
	3	F-3 (REGULATOR)	2	1250MM	
	4	HOB CHIMNEY SWITCH	1		
	5	EXHAUST FAN	1		
	6	BL-08 (UTILITY AREA)	1		
K-02	1	6-A SOCKET FOR HOB CHIMNEY	2	1600MM	
K-03	1	16-A SOCKET WITH SWITCH FOR REFRIDGERATOR	3	1350MM	
K-04	1	6-A SOCKET & SWITCH (GENERAL)	3	1250MM	
	2	16-A SOCKET & SWITCH FOR MICROWAVE	3		
K-05	1	6-A SOCKET WITH SWITCH FOR WATER PURIFIER	3	1600MM	
K-06	1	16-A SOCKET WITH SWITCH FOR WASHING MACHINE	3	1250MM	
GUEST BEDROOM					
GB-01	1	CL-9	1	1250MM	
GB-02	1	F-4 (ONLY REGULATOR)	2	600MM	
	2	BL-04	1		
	3	6-A SOCKET WITH SWITCH	3		
GB-03	1	CL-10	1	600MM	
	1	AC (SWITCH)	1		
	1	6-A SOCKET WITH SWITCH	3		
GB-04	1	TV POINT	1	600MM	
	2	6-A , 2 SOCKETS WITH 1 SWITCH	5		
GB-05	1	20A A.C BLACK BOX	2	2700MM	
TOILET -02					
T-01	1	BL-02	1		
	2	BL-03	1		
	3	GEYSER (SWITCH)	1	1250MM	
	4	EXHAUST FAN	1		
	5	6-A SOCKET WITH SWITCH	3		
T-02	1	16-A SOCKET FOR GEYSER	2	2700MM	


PALAVALAKEFRONT - SERENITY ASPI WING D

FIRST FLOOR - 3BHK UNIT (ROOM NO. 101)


SR.NO	SR.NO	POINT CONTROL	MODULES	HT. OF SB (BTM OF SB FROM SL)	REMARKS
MASTER TOILET					
MT-01	1	BL-06	1		
	2	BL-07	1		
	3	GEYSER (SWITCH)	1	1250MM	
	4	EXHAUST FAN	1		
	5	6-A SOCKET & SWITCH	3		
MT-02	1	16-A SOCKET FOR GEYSER	2	2700MM	
BEDROOM - 1					
BR-01	1	CL-11	1	1250MM	
BR-02	1	F-05 (ONLY REGULATOR)	2		
	2	BL-05	1	600MM	
	3	6-A SOCKET WITH SWITCH	3		
BR-03	1	CL-12	1		
	1	AC (SWITCH)	1	600MM	
	1	6-A SOCKET WITH SWITCH	3		
BR-04	1	TV POINT	1	600MM	
	2	6-A , 2 SOCKETS WITH 1 SWITCH	5		
BR-05	1	20A A/C BLACK BOX	2	2700MM	
MASTER BEDROOM					
MB-01	1	CL - 8 (2 WAY)	1	1250MM	
MB-02	1	CL-14	1		
	2	AC (SWITCH)	1	600MM	
	3	6-A SOCKET WITH SWITCH	3		
MB-03	1	CL-13	1		
	2	F-05 (ONLY REGULATOR)	2		
	3	6-A SOCKET WITH SWITCH	3	600MM	
	5	BL-10	1		
	6	CL-8 (2 WAY)	1		
MB-04	1	20A A.C BACK BOX	2	2700MM	
MB-05	1	TV POINT	1	1250MM	
	2	6A , 2 SOCKETS + 1 SWITCH	5		
TOILET - 01					
T-01	1	BL-12	1		
	2	BL-09	1		
	3	GEYSER (SWITCH)	1	1250MM	
	4	EXHAUST FAN	1		
	5	6-A SOCKET WITH SWITCH	3		
T-02	1	16-A SOCKET FOR GEYSER	2	2700MM	

LEGEND


	CEILING FAN		EXHAUST FAN
	CEILING LIGHT		FIRE ALARM SOUNDER/HOOTER
	WALL BRACKET	M.P.	MANUAL CALLPOINT
	AIR CONDITIONER		ACCESS P.CONT
	WALL BRACKET (CORRIDOR)		DOME CAMERA
	CONCEALED CEILING ROSE		GARDEN FOOT LIGHT
	FIRE PANEL	6A	6 AMP SWITCH & SOCKET




TELEVISION SWITCH BOARD DETAILS



SB 1



DETAILS FOR AC BACK BOX



DETAILS FOR BRACKET LIGHTS IN UTILITY AREA


GENERAL NOTE :-

1. ALL BRACKET LIGHTS IN TOILET @ 2000 MM FROM SLAB.
2. ALL BRACKET LIGHTS IN KITCHEN & UTILITY AREA ARE SUNK UTILITY AREA.
3. ALL BRACKET LIGHTS IN UTILITY AREA TO BE 100MM ABOVE BEAM BOTTOM (REFER ELEVATION)
4. ALL CEILING/WALL ROSE @ 2020 MM FROM SLAB.
5. ALL HEIGHTS FROM SLAB.
6. ALL SWITCH BOARDS & SOCKETS TO BE AT 900 FROM PLINTH LEVEL.
7. ALL SOCKET DIMENSIONS FOR 3& 6MD FOR FINISHED ED PLATE.
8. ***FOR 6Sq CM PELMET, AC BACK BOX LOCATION TO BE ESTABLISHED ON PELMET OUTER SURFACE AND COVERED WITH BLANK PLATE.***
9. ***SAME TO BE DONE FOR LIGHT POINTS IN PASSAGE AREA. THEIR LOCATION TO BE ESTABLISHED ON FALSE CEILING USING BLANK PLATES.***

GENERAL NOTES

1 : All dimensions are in millimeters and levels in meters unless specified otherwise.
2 : Do not scale the drawing; follow written dimensions.
3 : All dimensions are unfinished dimensions unless specified otherwise.
4 : Any discrepancies should be brought to the notice of the Architect prior to execution of job / procuring materials at site.
5 : This drawing is the property of Kapadia Associates and should not be reproduced, copied, handed over to a third party or used for any purpose other than for which it has been issued.
6 : This drawing is to be read in conjunction with all relevant structural & services drawings.

KEY PLAN



REVISION INDEX

REV.NO.	DATE	DESCRIPTION

CONSULTANTS

STRUCT BOMBAY CONSULTANTS.
Structural Consultants
Tel : 022-24937510,24933986
email : sbcbom@gmail.com

MICRO ENGINEERING
MEP Consultants
Tel : 0120-4558718
email : business@meindia.com

PBB
Planner /Landscape Architect
Tel : 079 6923054
email : landscapeindia@usg.net

STAMP & SIGN

NORTH

PROJECT TITLE	PROJ.NO
PALAVA-LAKEFRONT SECTOR- 4	**L-10518**
DRAWING TITLE	DWG.NO
AR-SERENITY WING D - ELECTRICAL LAYOUT (1ST FLOOR)	**801.2**
DRAWING STAGE	REV.NO
WORKING DRAWING	**R-00**

DRAWN	CHECKED	SCALE	DATE
BB	ES	AS.SPEC	29-01-2020

KAPADIA ASSOCIATES
architecture ▪ urban design
713-714, Tripolia Centre Dr. S.S. Rao Road, Off Annasaheb Rao Karve Road, Mumbai 400012
Tel : 91-22-4960 3958 / 59
Fax : 91-22-4960 3948
Email : kap@kapdi.in
Website : www.kapdi.in