BUROHAPPOLD ENGINEERING

BH-ZSG-SCH-P-0002

Section C & D - Drainage Manhole And Catchbasin Schedule

Revision	Description	Issued by	Date	Checked by
00	Tender	TA	Oct-15	TA
01	Tender	TA	Nov-15	PG

BH-ZSG-SCH-P-0002
Sewer Manholes

Sr. No.	Chamber Tag	Connecting to	Clear Size L (mm)xW(mm)	Mahole Cover Size (mm)	Ground Level (GL)	Invert Level (IL)	Remark
1	MH-001	MH-002	600x600	600x600	+98.15	+97.21	
2	MH-002	MH-003	900x800	600x600	+98.05	+96.975	
3	MH-003	MH-004	900x800	600x600	+98.03	+96.735	
4	MH-004	MH-005	900x800	600x600	+97.95	+96.485	
5	MH-005	MH-006	900x800	600x600	+98.90	+96.285	
6	MH-006	MH-007	600x600	600x600		+96.010	For Septic Tank
7	MH-007	MH-008	600x600	600x600		+95.890	For Septic Tank
8	MH-008	Soak Pit	600x600	600x600		+95.800	For Septic Tank

Copyright@Buro Happold Limited

BH-ZSG-SCH-P-0002
Storm Water Catch Basin

Sr. No.	Chamber Tag	Connecting to	Clear Size L (mm)xW(mm)	Ground Level (GL)	Invert Level (IL)
1	CB-001	CB-002	600x600	+97.8	+97.4
2	CB-002	CB-003	600x600	+97.6	+97.3
3	CB-003	CB-004	600x600	+97.6	+97.2
4	CB-004	CB-005	600x600	+97.6	+97.1
5	CB-005	Municipal Storm Water Drain	600x600	+97.6	+97.0
6	CB-006	CB-007	600x600	+98.09	+97.55
7	CB-007	CB-008	600x600	+98.03	+97.50
8	CB-008	Municipal Storm Water Drain	600x600	+97.96	+97.45

Copyright@Buro Happold Limited