AREA	TYPOLOGY	CONVENTIONAL BLDGS	NON CONVENTIONAL BLDGS	REMARKS	REFERENCE
STAIRCASE FINISH	A & B	one coat of smooth cement plaster on wall till ceiling + Enamel paint till 6'-0" ht. Above 6'-0" & ceiling raw	Directly Enamel paint till 6'-0" ht. Above 6'-0" & ceiling raw	22-Jun-15 In line with Design Staircase Policy	Email from Mayuresh
ELEC, LV & FHC DUCT	A & B	one coat internal plastering + two coats white wash	Direct two coats white wash		RFI
KITCHEN UTILITY AREA	A	18mm THK. MUTHYA finish External plaster + Texture paint	18mm THK. MUTHYA finish External plaster + Texture paint	Block works on either side of door	
		18mm THK. MUTHYA finish External plaster + Texture paint	Texture paint	RCC wall face	
		Birla putty + OBD	Birla putty + OBD	Slab soffit	
KITCHEN UTILITY AREA	B	18mm THK. MUTHYA finish External plaster + Texture paint	one coat smooth cement plastering + internal paint	Block works on either side of door	
		18mm THK. MUTHYA finish External plaster + Texture paint	one coat smooth cement plastering + internal paint	RCC wall face	
		Birla putty + OBD	Birla putty + OBD	Slab soffit	
LIVING ROOM / BEDROOM TERRACES	A & B	18mm THK. MUTHYA finish External plaster + Texture paint	Not applicable	Block work face	
		18mm THK. MUTHYA finish External plaster + Texture paint	Texture Paint	RCC wall face	
		18mm THK. MUTHYA finish External plaster + Non Texture paint	Non texture paint	Slab soffit	
TOILET PLUMBING SHAFT INTERNAL	A & B	18mm THK. MUTHYA finish External plaster + Non Texture waterproof paint	18mm THK. MUTHYA finish External plaster + Non Texture waterproof paint	Block work face	~~RFI reply 13 May~~
		18mm THK. MUTHYA finish External plaster + Non Texture waterproof paint	Non texture waterproof paint	RCC wall face	~~RFI reply 13 May~~
CHOWK AREA INTERNAL	A & B	18mm THK. MUTHYA finish External plaster + Non Texture waterproof paint	Not applicable	Block work face	~~RFI reply 13 May~~
		18mm THK. MUTHYA finish External plaster + Non Texture waterproof paint	Non texture waterproof paint	RCC wall face	~~RFI reply 13 May~~
PUJA AND STORE	A & B	Gypsum	Gypsum		RFI reply 13 May