TO BE W1

TO BE W1

THE CHOWK LEVEL TO BE 300MM LOWER THAN THE BLDG WITH HIGHER PLINTH.

OPENING AS PER VENDOR SPECIFICATION

300 MM GAP ONLY AT

REFER SERVICES DWG FOR

REFER ST. DETAILS

REFER ST. DETAILS

LINTEL PROVISION

LINTEL PROVISION

THIS BEAM SHALL BE ONLY AT THE OPEN ENDS OF THE CLUSTER

DIVIDE IN 3 EQ. PARTS

GROUND FLOOR WINDOW SCHEDULE

TYPE MARK	WIDTH	SILL HEIGHT	LINTEL HEIGHT
V1	1430	REFER FENESTRATION DWG 701 FOR CONVENTIONAL BLDGS VIZ. PRIMA, REGALIA & PASEO.	BEAM BOTTOM LEVEL. (i.e. BEAM DEPTH 650MM)
V2	900		
W1	1430		
W2	1350		
W4	750		
W5	750		
W7	600		
W9	1029		
SD1	1430		
SD2	1350		
SG2	1200		
O1	1017		

GROUND FLOOR DOOR SCHEDULE

TYPE MARK	WIDTH	**SILL HEIGHT**	LINTEL HEIGHT
D1	1050	0	BEAM BOTTOM LEVEL. (i.e. BEAM DEPTH 650MM)
D2	895	0	
D3	800	**0**	
D4	**850**	**0**	
DD1	750	0	
DD2	1500	450	
DD3	750	**450**	
FD1	1100	0	
FD2	1089	0	
LD1			
LD2			

SECTOR LEVEL KEY PLAN

NOTE :-
1) REFER SERVICES DWG FOR EXACT SLEEVES & CUTOUTS SETTING OUT/ HT. DETAILS .
2) REFER STRUCTURAL DWG FOR EXACT BEAM SIZES & PLINTH BEAM LEVELS & DETAILS .
3)THE CHOWK LEVEL SHALL BE 300MM LOWER THAN THE BLDG WITH HIGHER PLINTH.

LEGEND

- 100MM BLOCKWORK
- 125MM BLOCKWORK
- 150MM BLOCKWORK
- 200MM BLOCKWORK
- 230MM BLOCKWORK
- R.C.C. CONSTRUCTION
- 60 MM SUNK
- 125 MM SUNK
- 150 MM SUNK
- 200 MM FILL
- 300MM FILL

GENERAL NOTES

All dimensions are in millimeters and levels in meters unless specified otherwise.

Do not scale the drawing follow written measurements.

All dimensions are unfinished dimensions unless specified otherwise.

All discrepancies shouild be bought to notice of teh architect prior to execution of job/procuring material at site.

This drawing is property of Kapadia Associates and should not be copied,reproduced, handed over to a third party or used for any purpose other than for which it has been issued.

This drawing is to be read in conjunction with all relevant structural and services drawing.

A1 TYPE 02 - CONVENTIONAL GROUND FLOOR

1 : 50

REVISION INDEX

No.	Date	Description
R1	26.9.16	BLOCKWORK ADDITION AS MARKED & LINTEL PROVISION.
R2	7.10.16	BLOCKWORK ADDITION AS MARKED & LINTEL PROVISION.
R3	19.10.16	BLOCKWORK ADDITION AS MARKED & LINTEL PROVISION.ALSO ADDED BLOCKWORK ABOVE CANOPY.

CONSULTANTS
TCE-TATA CONSULTING ENGINEERS LTD.
Infra Structure Consultants
Tel : 91 22 61148181
email : www.tce.co.in

WSP
Services
Tel : 91 120480 8400
email : www.wspgroup.com

CONSULTANTS
STRUCT BOMBAY CONSULTANTS
Civil & Structural Consultants
Tel : 022-24937510 / 24933986
email : sbcbom@gmail.com

PBB
Planner / Landscape Architect
Tel : 079 6923054
email : landscapeindia@usg.net

NORTH

STAMP & SIGN

DRAWN	N.B.	PROJECT TITLE	LODHA PALAVA A1 CONV. TYPE 01
CHECKED	NS	DRAWING TITLE	AR/C/A1/TYP 02_GRD FLR PLAN
SCALE	1:50	DRAWING STAGE	V.F.C.
REV. NO.	R3	PROJ. NO.	L6513
		DWG. NO.	201.1
		DATE	19.10.16

KAPADIA ASSOCIATES
architecture+urban design
12-114
Peninsula Centre,Dr. S.S. Rao Road,
Off Ambedkar Road,Parel East,
Mumbai 400012
Tel : 91-22-6660 2838 / 39
Fax : 91-22-6660 2844
E-mail : kapl@kapl.in
Website: www.kapl.in