Superior Art

Near Oshiwara Bridge, Jogeshwari (W) Gala No - 10, Bhori Estate Road, Off SV Road MUMBAI-400102

Date - 31/12/2021

To.
Lodha Excelus,
Level L2, Apolla Mill Compound,
N.M. Joshi Marg, Mahalaxmi,
Mumbai - 400 011

Estimate of External Manpada Metro LED sign

SIGN TYPE	Image	Specification	Qty.	Rate Per Nos.	Amount (Rs)
Exterior LED Sign		**A** LETTERS SHALL BE MADE OUT OF ALUMINUM LETTERS 5" SIDE DEPTH SIDE FINISHED - BLACK COLOR **B** FRONT FACE OF THE LETTERS SHALL BE OF 3MM THICK. TRANSLUCENT ACRYLIC WITH 3M DAY & NIGHT PERFORATED FILM TO BE PASTED ONTO FRONT FACE OF ACRYLIC DAY TIME APPEARANCE : BLACK NIGHT TIME APPEARANCE : WHITE **C** SUITABLE WHITE POWER LED LIGHTS WHITE MEDIUM POWER OF COLOR TEMP 6100K SHALL BE USED FOR ILLUMINATION LED SHALL BE Ip65 RATING, POWER SUPPLY EXTERIOR GRADE OF BRAND GIVING 5 YEAR WARRANTY.	**1**	**3,23,000.00**	**3,23,000.00**
				Sub. Total	**3,23,000.00**
				GST @ 18%	**58,140.00**
				Gr. Total	**3,81,140.00**

Chetan Koli
09819008518

Terms and condition

The above estimate is valid for 30 days from date.
.Transport Lodging Boarding will be additional at actual.
The above work will be completed within 30 days from the date of receipt of PO and advance.
50% advance payment balance on truck loading and balance immediately after delivery of material.
In case of delay in providing of facilities and any other work within clients scope idle labor charges for the installation team will be Rs. 800.00 per person per day.
All the requisite permission along with entry permits for installation team to be arranged by client at their cost.
Necessary way bills and required documents to be provided by client at the time of confirmation of order.
All the artworks in digital format to be provided by client at their cost
Civil work in the scope of the client.
Metal Structure cost will be dependent on actual site location which will be at actual.
Scaffolding ,Zoom Lift, Boom etc include in above rate.