PROJECT - Lodha Palava Project							
M/s Lodha Group- Mumbai							
Ms. Gauri Panchal-9619050363							
SR. NO.	DESCRIPTION OF ITEMS	UNIT	QTY	RATE IN INR		AMOUNT IN INR	
				SUPPLY	INSTALLATION	SUPPLY	INSTALLATION
	FIRE CURTAINS						
1	**Fire Curtains From Orient Fire curtains**						
	"Fire Curtains" with galvanized MS head box, **size(200X200mm)** powder coated, side guides size(**53x100mm)** along with adjustment channels & bottom bars with motors for power up operation with standard battery backup & operated system safe fixed into steel rollers with woven glass fibre fabric, reinforced with stainless steel wire having micronized aluminium polymer coating on each side of the fabric (silver/grey) with the necessary control panel & all installation assemblies & accessories required to complete the installation. The operation shall be suitable for dedicated 240 Volts UPS, 50 Hz AC supply. Complete system shall be tested in accordance with EN 1634-1 (for 120 minutes Integrity & tested at 1000°C) BS 476-22.8 and BS 7346-3. Quoted rate shall include necessary **"Emergency Retract Switch"** on both sides of the curtain along with necessary control panel housed within the provided false ceiling depth with suitable supports. Vendor/Manufacturer to submit valid Test Report for the complete systems and not just for fabric from an independent international accredited laboratory. The Test Report of complete system should not be more than 5 years old. Vendor/Supplier should duly submit current dated authorization letter from the manufacturer or principal that he is representing :**Make- Orient Fire Curtains**						
	Fire Curtains						
1.1	**Automatice Fire Curtains : 2500mm (W) X 2900mm (H)**	nos	1	200000	15000	200000	15000
Total						**200000**	**15000**
Special Discount 15%						30000	
Total Amt (Supply + Installation)						170000	30000

GST Extra @ 18%

Transportation Extra & Mathari, Unloading, Lifting will Client Scope.

1. Operation by a battery back-up control unit which requires a 240 volt mains power supply by others.
2. Price given for 120min integrity Fire/Smoke Curtain at 1000 Degree Celsius.
3. Manufacture; 2-4 weeks after confirmation of order, Shop Drg approval and deposit received.
4. We will accept no additional costs for delay in delivery.
5. Powder coated finish on hood, guides and bottom rail in standard RAL colour.
6. Controlled decent and key switch for regular testing.
7. Separate order to be issue of Supply & Installation.
8. Following things are covered in the installation scope-Installation of fire curtain, Barrel, Control Box, two way switches, Override switch, Side Guides, Top Box as per tested system. All Interconnections between our components as mentioned above are in our scope.
9. However any civil work/civil modification location to install the curtain to be done by client.
10. Any scaffolding support to hang the curtain will be provided by the client as curtain required
full back side support for the motor/hood assembly.
11. Any concealing/cutting work at location to be done by client.
12. AC Main power at all curtain location (near the Control Panel) will be provided by client. Electrical Connections and supply till control panel and override switch.
13. Items made to clients specifications.
14. Sizes given as shown in above table.
15. Supply only: Units pre-assembled with limits set to an approximate height.
16. Drawings required before manufacture.
17. All goods will remain the property of Orient Fire Curtains India Pvt.Ltd (Subsidiary of M/s Smoke & Fire Curtains Ltd.UK) until paid for in full. We reserve the right to remove any units fitted by ourselves or others until full payment is received.

Kind Regards

Lalit Mohan
Orient Fire Curtains India Pvt Ltd
8826700886